

Table detailing types of materials and quantities deposited or removed below MHWS during the proposed bridge maintenance work at six bridges

		Connel	Ballachulish	Dornie	Skye	Carrich	Cromarty
Activities	Material						
Minor concrete repairs (Hydrodem) (discharge)	<i>Water</i>	25,000 litres/day	25,000 litres/day	25,000 litres/day	25,000 litres/day	25,000 litres/day	25,000 litres/day
Minor concrete repairs (removal)	<i>Concrete</i>	5m3	5m3	10m3	10m3	10m3	10m3
Minor concrete repairs (deposit)	<i>Concrete</i>	5m3	5m3	10m3	10m3	10m3	10m3
Scour repair (deposit)	<i>Rock armour</i>	500m3	n/a	600m3	n/a	n/a	5000m3
	<i>Sand</i>	20m3	n/a	50m3	n/a	n/a	200m3
	<i>Gravel</i>	20m3	n/a	50m3	n/a	n/a	200m3