

Table detailing types of materials and quantities deposited or removed from below MHWS during the proposed bridge maintenance work

		Dornoch
Activities	Material	
HydroDemolition	<i>Water</i>	25,000 litres/day
Bridge Levelling	<i>Jacks (Temp)</i>	1T
	<i>Scaffolding (Temp)</i>	15T
	<i>Steel Shims</i>	5T
Minor concrete repairs (removal)	<i>Concrete</i>	10m3
Minor concrete repairs (deposit)	<i>Concrete</i>	10m3