ARGYLL & BUTE COUNCIL --- DEVELOPMENT AND INFRASTRUCTURE SERVICES



Proposed Section Through Bridge

1:20



Proposed new mortar with darkening agents added to ensure new mortar matches existing mortar. Face of pointing to be keyed troweled to match the

Wingwall and abutment

To be repointed with suitable underwater, marine and saltwater resistant mortar with a minimum compressive strength of 50Mpa after 28 days as per specification. Injection method required to ensure deep voids are filled as some voids have been recorded up to 1.1m deep.

NOTES:

TITLE

- 1. All dimensions are in millimetres unless noted otherwise.
- 2. Do not scale from this drawing.
- 3. Dimensions have been taken from historic drawing, the contractor should confirm exact dimensions onsite.
- 4. The public utilities shown are taken from utility plans, the contractor should confirm the exact locations on site prior to the breaking of the ground by undertaking CAT and GENI scans.
- 5. To be read in conjunction with Works Information, Drawing Series 00019-32 and Specification.

© Crown copyright and database right 2020. All right reserved. Ordnance Survey Licence number 100023368

Pointing Detail

Not to Scale

Clachan	Bridge,	Isle o	of Sei
Cons	truction	Deta	ils

_	_	-	-	-	-	Construction Details
-	_	-	_	-	-	
	BEVISION	INIT.	DATE	INIT.	DATE	DESIGN OFFICE, MANSE BRAE,
	REVISION	DESIGNED BY APPR		ROVED BY	LOCHGILPHEAD, ARGYLL,PA31 8RD	

	Head of Roads and Infrastructure Services Jim Smith					
	DESIGNED BY	SAJG	DRAWING NUMBER:			
	DRAWN BY	SAJG	00019-32 /	605		
	CHECKED BY	КН	SCALE:	Argvll		
	APPROVED BY	ES		Bute		
	DATE 22/12/	20	AJ	COUNCIL		