



DETAIL 'A'
SCALE 1:25




STEELWORK NOTES

- 1 THE SPECIFICATION SHALL BE THE NATIONAL STRUCTURAL STEELWORK SPECIFICATION (NSSS) FOR BUILDING CONSTRUCTION. CURRENT EDITION PUBLISHED BY BCSA/SCI.
- 2 ALL STRUCTURAL STEELWORK SHALL BE IN ACCORDANCE WITH BS EN 1993 AND UK NATIONAL ANNEX.
- 3 STEEL GRADE: EN 10025-2 S355 J0.
- 4 ALL HOLLOW SECTIONS TO BE HOT FINISHED (NOT COLD FORMED). STEEL GRADE S355 J0H TO BS EN 10210.
- 5 ALL BOLTS TO BE GRADE 8.8 GALVANISED UNLESS NOTED OTHERWISE.
- 6 ALL WELDING SHALL BE CARRIED OUT IN ACCORDANCE WITH BS EN 1090-2. ROUTINE TESTING OF FABRICATION AND ON-SITE WELDING SHALL BE CARRIED OUT IN ACCORDANCE WITH THE NATIONAL STRUCTURAL STEELWORK SPECIFICATION. RECORDS SHALL BE KEPT OF VISUAL INSPECTIONS, NON-CONFORMANCES, CORRECTIVE ACTIONS, AND NON-DESTRUCTIVE TESTING (NDT).
- 7 STEELWORK SHALL COMPLY WITH BS EN 1090-2 FOR EXECUTION CLASS EXC2 AND TOLERANCE CLASS 1.
- 8 ATMOSPHERIC CORROSIVITY CATEGORY TO BS EN ISO 12944-2 IS CATEGORY C3.
- 9 STRUCTURAL STEELWORK TO BE HOT DIPPED GALVANISED WITH MINIMUM COATING OF 140 MICRONS.
- 10 THE STEELWORK FABRICATOR SHALL PRODUCE CLEAR AND ACCURATE SHOP DETAILS AND ARRANGEMENT DRAWINGS FOR FABRICATION AND ERECTION PURPOSES, WHICH MUST BE SUBMITTED TO THE ENGINEER FOR COMMENT AT LEAST TWO WEEKS PRIOR TO COMMENCEMENT OF FABRICATION. THE ENGINEER'S COMMENT ON SHOP DRAWINGS SHALL NOT RELIEVE THE STEELWORK FABRICATOR OF THEIR RESPONSIBILITY FOR ACCURACY OF THE DIMENSIONS, SETTING OUT, LEVELS, OR CONNECTIONS.
- 11 THE CONTRACTOR IS RESPONSIBLE FOR THE ACCURACY OF ALL DIMENSIONS, CORRECT SETTING OUT AND ERECTION OF THE STEELWORK ON SITE.
- 12 THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL THE TEMPORARY WORKS NECESSARY TO ENSURE THE STABILITY OF STRUCTURES AT ALL TIMES DURING CONSTRUCTION.
- 13 ALL MATERIALS, FABRICATION AND WORKMANSHIP TO BE IN ACCORDANCE WITH THE NATIONAL STEELWORK SPECIFICATION FOR BUILDING IN CONSTRUCTION, 7. EDITION.
- 14 FILLET WELDS TO BE A MINIMUM OF 6mm TO FORM A CONTINUOUS SEAL AROUND THE CONNECTING MEMBERS UNO.

ALL WALKWAYS, HANDRAILS AND SUPPORT STEELWORK TO BE GALVANISED IN ACCORDANCE WITH THE SPECIFICATION.

NOTES

1. FOR BERTH PLAN REFER TO DRAWING No. 235014-sk'A'.
- 2.



/	5.3.25	FIRST ISSUE - PLANNING	G.B.	M.H.W.
REV	DATE	REVISION DESCRIPTION	DRN	VER

THIS DRAWING IS COPYRIGHT. DO NOT SCALE FROM THIS DRAWING.

Arch
Henderson
1919

142 St. Vincent Street, Glasgow G2 5LA.
Tel : 0141 227 9060 - Fax : 0141 249 9542
www.arch-henderson.co.uk - email : glasgow@arch-henderson.co.uk

Offices in : Aberdeen, Dundee, Falkland Islands, Glasgow, Inverness, Lerwick, Southampton, Stromness and Thurso

Civil Engineers
Structural Engineers
Principal Designers
Architects
Geotechnical services
Environmental services

PROJECT :
Western Ferries (Clyde) Ltd.
Kilmun Pier Berth

TITLE :
NEW WORKS
Walkway Details (Sheet 1)

DRAWN : G.B.	DATE : 5.3.25	VERIFIED : M.H.W.	APPROVED :
SCALE : (A1) 1:25, 1:10		DRAWING STATUS : PLANNING	
DRAWING No : 235014-008		REV : /	

DO NOT SCALE