

To be read in conjunction with **Section 2.4** of Licence MS-00011194

To summarize:

Our revised proposal will utilise the same permanent works as per current license. No changes.

Our revised proposal for temporary works will utilise the same number of sheet piles combined into a larger phase to create main cofferdam.

Our revised proposal for temporary works will introduce the following changes:

- Removal of stoned causeway/ twinwall culvert – this will be replaced with the floating pontoon bridge
- Addition of scaffold A frame (Flexi-dam) dam section to strengthen previously proposed 1tonne bags and visqueen arrangement

Detailed comments below:

Materials to be **permanently** deposited in the course of the Licensed Activity:

- 1076 tonnes, concrete mattresses
- 120 no. precast concrete L walls
- 80 cubic metres, poured concrete
- 2850 tonnes, gravel
- 2850 tonnes, cobbles
- 1760 tonnes, boulders

All permanent works materials and quantities will remain unchanged. Permanent work design remains unchanged.

Previously Licensed conditions will remain the same.

Materials to be **temporarily** deposited in the course of the Licensed Activity:

- 600 metres squared, Visqueen plastic sheet
- 880 tonnes, boulders
- Approximately 12 no. 1.2 metres x 6 metres, twin wall pipes – no longer required
- 150 no. tonne bags of stone
- 24tonnes, steel scaffolding – Flexi-dam
- 15tonnes, steel casings CHS – pontoon bridge anchors
- 320m2 – floating pontoon bridge (part submerged)

Materials to be removed in the course of the Licensed Activity:

- 225 tonnes, concrete
- 5700 tonnes, gravel
- 2850 tonnes, cobbles

Permanent work design remains unchanged.

Previously Licensed conditions will remain the same.