



<div>Drawing Number</div> <div>19/NW/0309/005/003</div>		<div>Notes</div> <div>General</div> <div><div>1. See drawing 19/NW0309/005/001 for location details</div><div>2. See drawing 19/NW/0309/005/002 for general arrangement of works.</div><div>3. Reference should be made to Designer's Risk Register and Method Statement for the works</div><div>4. Site Environmental Management Plan should be adhered to at all times</div></div> <div>Imported Fill</div> <div><div>5. All imported material should be in accordance with SHW Tab 6/1.</div><div>6. Structural fill to the rear of modular block wall / armour stone revetment should consist of 6/1 material with the final 300mm depth comprising Type 1 material in accordance with SHW Cl. 803.</div></div> <div>Geotextile</div> <div><div>7. Geotextile to have minimum CBR resistance of 11kN and minimum tensile strength of 60kN/m.</div></div> <div>Grouting</div> <div><div>8. Minimum C20 strength foam concrete.</div><div>9. Mortar for superficial pointing/backfill shall comprise of cement mortar with cement to sand ratio of 1:2.5 to 3:5 (designation ii) in accordance with SHW Cl. 2404.</div></div> <div>Armour Stone</div> <div><div>10. Minimum 1m -1.5m grading of Armour Stone in accordance with CIRIA C742.</div></div>																					
<div>Existing Stone Revetment (Expected Random Rubble Fill)</div> <div>Verge ~ 0.6m</div> <div>Carriageway ~ 6.1m</div> <div>3m</div> <div>Existing Stone Revetment (Expected Random Rubble Fill)</div> <div>MHWS ~ 7m From Revetment Tope</div> <div>Foreshore</div>												<div>Existing Stone Revetment (Expected Random Rubble Fill)</div> <div>Verge ~ 0.6m</div> <div>Carriageway ~ 6.1m</div> <div>3m</div> <div>Existing Stone Revetment (Expected Random Rubble Fill)</div> <div>MHWS ~ 7m From Revetment Tope</div> <div>Foreshore</div>											
<div>Existing Stone Wall</div> <div>Footway ~ 1m</div> <div>Existing Carriageway ~ 6.1m</div> <div>6m</div> <div>Existing Stone Revetment (Expected Random Rubble Fill)</div> <div>MHWS ~ 7M From Revetment Tope</div> <div>Foreshore</div>												<div>Existing Stone Wall</div> <div>Footway ~ 1m</div> <div>Existing Carriageway ~ 6.1m</div> <div>6m</div> <div>Existing Stone Revetment (Expected Random Rubble Fill)</div> <div>MHWS ~ 7M From Revetment Tope</div> <div>Foreshore</div>											
<div>Existing Stone Revetment (Expected Random Rubble Fill)</div> <div>Verge ~ 0.6m</div> <div>Carriageway ~ 6.1m</div> <div>3m</div> <div>Existing Stone Revetment (Expected Random Rubble Fill)</div> <div>MHWS ~ 5m From Revetment Tope</div> <div>Armour Stone Height of 1 - 2 Blocks Maximum from Shore Level</div> <div>1m - 1.5m Grade Armour Stone</div> <div>Area of Voiding To Be Filled With Foam Concrete</div> <div>RG11 Terram</div> <div>Foreshore</div>												<div>Existing Stone Revetment (Expected Random Rubble Fill)</div> <div>Verge ~ 0.6m</div> <div>Carriageway ~ 6.1m</div> <div>3m</div> <div>Existing Stone Revetment (Expected Random Rubble Fill)</div> <div>MHWS ~ 5m From Revetment Tope</div> <div>Armour Stone Height of 1 - 2 Blocks Maximum from Shore Level</div> <div>1m - 1.5m Grade Armour Stone</div> <div>Area of Voiding To Be Filled With Foam Concrete</div> <div>RG11 Terram</div> <div>Foreshore</div>											
<div>Existing Stone Wall</div> <div>Footway ~ 1m</div> <div>Existing Carriageway ~ 6.1m</div> <div>6m</div> <div>Existing Stone Revetment (Expected Random Rubble Fill)</div> <div>1m - 1.5m Grade Armour Stone</div> <div>Area of Voiding To Be Filled With Foam Concrete</div> <div>Armour Stone Height of 2 - 3 Blocks Maximum from Shore Level</div> <div>RG11 Terram</div> <div>MHWS Intrusion ~ 3M</div> <div>Foreshore</div>												<div>Existing Stone Wall</div> <div>Footway ~ 1m</div> <div>Existing Carriageway ~ 6.1m</div> <div>6m</div> <div>Existing Stone Revetment (Expected Random Rubble Fill)</div> <div>1m - 1.5m Grade Armour Stone</div> <div>Area of Voiding To Be Filled With Foam Concrete</div> <div>Armour Stone Height of 2 - 3 Blocks Maximum from Shore Level</div> <div>RG11 Terram</div> <div>MHWS Intrusion ~ 3M</div> <div>Foreshore</div>											
<div>Existing N2WS Flexbeam VRS With Concrete Log Foundation</div> <div>Existing Carriageway ~ 6.1m</div> <div>Existing Stone Revetment (Expected Random Rubble Fill)</div> <div>1m - 1.5m Grade Armour Stone</div> <div>Area of Voiding To Be Filled With Foam Concrete</div> <div>Armour Stone Height of 2 - 3 Blocks Maximum from Shore Level</div> <div>RG11 Terram</div> <div>MHWS Intrusion ~ 3M</div> <div>Foreshore</div>												<div>Existing N2WS Flexbeam VRS With Concrete Log Foundation</div> <div>Existing Carriageway ~ 6.1m</div> <div>Existing Stone Revetment (Expected Random Rubble Fill)</div> <div>1m - 1.5m Grade Armour Stone</div> <div>Area of Voiding To Be Filled With Foam Concrete</div> <div>Armour Stone Height of 2 - 3 Blocks Maximum from Shore Level</div> <div>RG11 Terram</div> <div>MHWS Intrusion ~ 3M</div> <div>Foreshore</div>											
<div>Existing N2WS Flexbeam VRS With Concrete Log Foundation</div> <div>Existing Carriageway ~ 6.1m</div> <div>Existing Stone Revetment (Expected Random Rubble Fill)</div> <div>6m</div> <div>Existing Stone Revetment (Expected Random Rubble Fill)</div> <div>MHWS ~ 7M From Revetment Tope</div> <div>Foreshore</div>												<div>Existing N2WS Flexbeam VRS With Concrete Log Foundation</div> <div>Existing Carriageway ~ 6.1m</div> <div>Existing Stone Revetment (Expected Random Rubble Fill)</div> <div>6m</div> <div>Existing Stone Revetment (Expected Random Rubble Fill)</div> <div>MHWS ~ 7M From Revetment Tope</div> <div>Foreshore</div>											
<div>Design Cross-Section Ch. (440-660) (976-996) ~ NTS</div>												<div>Design Cross-Section Ch. (440-660) (976-996) ~ NTS</div>											
<div>Project</div> <div>A83 Inveraray Sea Wall Repair</div>												<div>Project</div> <div>A83 Inveraray Sea Wall Repair</div>											
<div>Title</div> <div>Design Cross Sections</div>												<div>Title</div> <div>Design Cross Sections</div>											
<div>Drawing No.</div> <div>19/NW/0309/005/003</div>												<div>Drawing No.</div> <div>19/NW/0309/005/003</div>											
<div>Scale</div> <div>NTS</div>												<div>Scale</div> <div>NTS</div>											
<div>Designed</div> <div>BC</div>												<div>Designed</div> <div>BC</div>											
<div>Drawn</div> <div>BC</div>												<div>Drawn</div> <div>BC</div>											
<div>Checked</div> <div>CRF</div>												<div>Checked</div> <div>CRF</div>											
<div>Approved</div> <div>KR</div>												<div>Approved</div> <div>KR</div>											

Drawing Number									
19/NW/0309/005/003									
Notes General <ol style="list-style-type: none"> See drawing 19/NW/0309/005/001 for location details See drawing 19/NW/0309/005/002 for general arrangement of works. Reference should be made to Designer's Risk Register and Method Statement for the works Site Environmental Management Plan should be adhered to at all times Imported Fill <ol style="list-style-type: none"> All imported material should be in accordance with SHW Tab 6/1. Structural fill to the rear of modular block wall / armour stone revetment should consist of 61/2 material with the final 300mm depth comprising Type 1 material in accordance with SHW Cl. 803. Geotextile <ol style="list-style-type: none"> Geotextile to have minimum CBR resistance of 11kN and minimum tensile strength of 60kN/m. Grouting <ol style="list-style-type: none"> Minimum C20 strength foam concrete. Mortar for superficial pointing/backfill shall comprise of cement mortar with cement to sand ratio of 1:2.5 to 3.5 (designation ii) in accordance with SHW Cl. 2404. Armour Stone <ol style="list-style-type: none"> Minimum 1m -1.5m grading of Armour Stone in accordance with CIRIA C742. 									
Do not scale this drawing									
Rev	Date							Checked	
Status									
CONSTRUCTION									
Rev.									
01									
Client									
 <small>Transport Scotland</small>									
									
Project									
A83 Inveraray Sea Wall Repair									
Title									
Design Cross Sections									
Drawing No.	19/NW/0309/005/003						Date	OCT 19	
Scale	NTS								
Assigned	BC	Drawn	BC	Checked	CRF	Approved	KR		