Table detailing types of materials and quantities deposited or removed bel maintenance work at six bridges

		Connel	Ballachulish	Dornie
Activities	Material			
Minor concrete repairs				
(Hydrodem) (discharge)	Water	25,000 litres/day	25,000 litres/day	25,000 litres/day
Minor concrete repairs				
(removal)	Concrete	5m3	5m3	10m3
Minor concrete repairs				
(deposit)	Concrete	5m3	5m3	10m3
	Rock armour	500m3	n/a	600m3
Scour repair (deposit)	Sand	20m3	n/a	50m3
	Gravel	20m3	n/a	50m3

ow MHWS during the proposed bridge

Skye	Carrich	Cromarty
25,000 litres/day	25,000 litres/day	25,000 litres/day
10m3	10m3	10m3
10m3	10m3	10m3
n/a	n/a	5000m3
n/a	n/a	200m3
n/a	n/a	200m3