



GENERAL NOTES

- ALL LEVELS ARE IN METRES AND RELATE TO ORDNANCE DATUM.
- ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE.
- CHART DATUM IS 2.1m BELOW ORDNANCE DATUM.
- | | | |
|------|----------|----------|
| HAT | +2.60mOD | +4.70mCD |
| MHWS | +2.00mOD | +4.10mCD |
| MHWN | +1.10mOD | +3.20mCD |
| MSL | +0.31mOD | +2.41mCD |
| MLWN | -0.50mOD | +1.60mCD |
| MLWS | -1.40mOD | +0.70mCD |
| LAT | -2.00mOD | +0.10mCD |
- FOR LADDER AND GRAB CHAIN DETAILS REFER TO DRAWING 2226/102.
- FOR CONCRETE REPAIRS TO QUAY WALL REFER TO DRAWING 2226/103.
- FOR SCOUR HOLE REPAIRS AND HAND RAIL DETAILS REFER TO DRAWING 2226/104.
- FOR CONCRETE SLAB REPAIRS REFER TO DRAWING 2226/105.
- FOR WAVE WALL REPAIRS AND MOORING RING DETAILS REFER TO DRAWING 2226/106.
- FOR CONCRETE FACING REPAIR REFER TO DRAWING 2226/107
- FOR CONCRETE BRIDGE REPLACEMENT REFER TO DRAWING 2226/108
- FOR SLAB EDGE REPAIR REFER TO DRAWING 2226/109

LEGEND
 MR1 – MOORING RING
 3.836(Q) – QUAY LEVEL
 3.836(B) – BED LEVEL
 AREA OF SHINGLE DEPOSITS TO BE REMOVED
 1270m²

A	01.08.22	"THE CROWN ESTATE" AMENDED TO "CROWN ESTATE SCOTLAND"	JG	TR	TR
REV	DATE	DETAILS	DRAWN	CHK'D	APP'D

AMENDMENTS

CLIENT
CROWN ESTATE SCOTLAND

PROJECT
PORTGORDON HARBOUR MAINTENANCE AND REPAIRS

Wallace Stone
 Consulting Civil Engineers

GLASGOW 0141 554 8233 glasgow@wallacestone.co.uk	DINGWALL 01349 866775 dingwall@wallacestone.co.uk
HEBRIDES 01851 612454 hebrides@wallacestone.co.uk	

DRAWING TITLE
GENERAL LAYOUT

DRAWN JHG	CHECKED NG	APPROVED TR
DATE 11.07.22	DATE 28.07.22	DATE 28.07.22

SCALE (A1) 1:500
 REVISION **A**
 STAGE **TENDER**

PROJECT No. 2226	DRAWING No. 101
----------------------------	---------------------------