


MAGALLANES TIDAL ENERGY | BERTH 4 ARRAY

Project Information Summary

[January 2024]



Purpose

This Project Information Summary gives a high-level view of Magallanes Tidal Energy, the device, and the proposed project. This document is the foreword to the project’s Marine Licence application, and will feed into the rest of the application supporting documentation, including but not limited to the following documents:

- Project Environmental Monitoring Plan
- Navigational Risk Assessment Addendum
- Decommissioning Program
- Third Party Verification

Document History

Revision	Date	Description	Originated by	Reviewed by	Approved by
A	04/11/23	First Draft	JH		

Disclaimer

In no event will Magallanes Tidal Energy Ltd, the European Marine Energy Centre Ltd or their employees or agents, be liable to you or anyone else for any decision made or action taken in reliance on the information in this report or for any consequential, special or similar damages, even if advised of the possibility of such damages. While we have made every attempt to ensure that the information contained in the report has been obtained from reliable sources, neither the authors nor Magallanes Tidal Energy Ltd or the European Marine Energy Centre Ltd accept any responsibility for and exclude all liability for damages and loss in connection with the use of the information or expressions of opinion that are contained in this report, including but not limited to any errors, inaccuracies, omissions and misleading or defamatory statements, whether direct or indirect or consequential. Whilst we believe the contents to be true and accurate as at the date of writing, we can give no assurances or warranty regarding the accuracy, currency or applicability of any of the content in relation to specific situations or particular circumstances.

Contents

1	Introduction	1
1.1	Company background	1
1.2	Technology background	2
1.3	Project background	3
2	Technology	4
2.1	Device Description	4
2.2	Mooring system	10
2.3	Materials used	13
2.4	Third Party Verification (TPV)	14
3	Project Description	15
3.1	Onshore Assets	15
3.2	Offshore Location	15
3.3	Installation method	17
3.4	Removal method	22
3.5	Anticipated vessel traffic to site	23
3.6	Device monitoring systems	24
4	Proposed Schedule	26

List of Figures

Figure 1: Evolution of the Magallanes Tidal Energy Technology	2
Figure 2: Launch of the Prototype ATIR Platform	3
Figure 3: TIR Platform Showing ‘Blocks’	4
Figure 4: Indicative Overall Dimensions of the Device.....	5
Figure 5: Main Components of the ATIR Platform	6
Figure 6: External View of the Platform (Upper Block).....	6
Figure 7: Internal View of the Upper Block	7
Figure 8: View Looking up into the Mast (Vertical Block) from the Nacelle (Lower Block).....	7
Figure 9: Gearbox in the Nacelle (Lower Block)	8
Figure 10: Diagram of Electrical Power Generation from Tidal Currents	8
Figure 11: Ring cable concept.....	9
Figure 12: Star cable concept	9
Figure 13: Examples of Rock Bags and Concrete Mattresses.....	10
Figure 14: Indicative Scheme for the Mooring System	10
Figure 15: Strataloc Anchor (Left). Tricone (Centre) and Core (Right) Anchor Piles that will be considered for use at the site (Developed by Leask Marine)	11
Figure 16: Indicative Scheme with Gravity Anchors	12
Figure 17: Single point mooring system schematic prior to device installation (top), and during deployment (bottom)	13
Figure 18: Chart showing EMEC’s Fall of Warness test site and the Magallanes deployment area	16
Figure 19: Images Showing drill rig loadout, deployment to seabed and drilling.....	18
Figure 20: Map showing area of EMEC’s scale tidal test site, Shapinsay Sound.....	19
Figure 21: Map showing area of device temporary deployment at Deerness Sound	20
Figure 22: Map showing area of device temporary deployment at Scapa Bay.....	21
Figure 23: Multi-cat vessels MV C-Odyssey (left) and MV C-Fenna (right).....	22

List of Tables

Table 1: Proposed list of materials to be used.....	14
Table 2. Location of [Project Name]	17
Table 3: Attachment points at EMEC’s Shapinsay Sound test site	19
Table 4: Boundary of lease area for temporary mooring at Deerness anchorage.....	20
Table 5: Vessel activity associated with the proposed array project	23
Table 6: Platform monitoring systems	24

1 Introduction

1.1 Company background

Magallanes Tidal Energy is a leading developer of tidal energy technology. We are the recently established UK branch of Magallanes Renovables and have been set up specifically to commercialise the Magallanes technology, leveraging the unparalleled expertise of the UK supply chain to do so. Magallanes Tidal Energy is registered in Scotland, established in 2020.

Founded in 2007 Magallanes Renovables was created with the sole purpose of developing and commercialising a cost-effective tidal technology, overcoming the hurdles that have historically held the sector back. Our philosophy is simplicity and cost-effectiveness, which has led us to develop breakthrough systems, solving the many challenges encountered with innovative and cost-effective solutions.

Our technology is centered around a simple and reliable surface floating platform that leverages existing technology from the mature wind and naval industries, minimising technology risk. Our platforms deliver high output with low installation and maintenance costs.

We are a highly experienced multidisciplinary team with innovation, sustainability and quality as our core values. We have deployed and tested a full-scale platform in the unforgiving environment of the Orkney Islands. Previously we developed and tested 2 scale models to inform the full-scale design.

Key team experience

Our multidisciplinary and highly skilled team has been the main driver of our success, each individual is in charge of one of the working areas for technology development. Important decisions are taken in quorum and teamwork is part of our open working structure.

In addition, Magallanes Renovables has collaborated very closely with skilled partners in different business and technology areas needed to develop a ground-breaking system in tidal energy generation.

Since its inception, the company has been involved in multiple R&D projects focused on developing floating tidal turbines.

Work completed:

- 2007 to 2011 – concept development and evaluation including partial systems tests at small scale – e.g., 1:30 turbine and rotor
- 2011 to 2012 - 1:10 scale model constructed to evaluate and validate the concept. Prototype tested in Bay of Vigo and Scotland with positive results.
- 2013 to 2015 – Design of full-scale platform and systems.
- 2016 to 2017 – Construction of full scale, 1.5MW platform in Spain
- 2018 to 2018 - Sea-trials of full-scale platform around Vigo.
- 2019 onwards - Platform installed and grid-connected at EMEC, Scotland in early 2019, where it operates currently.
- 2020 – upgrades to key systems on the full scale platform

The accumulated project experience in areas of structural design, marine operations, control systems, energy production, mooring systems, etc. has allowed us to achieve the goal of having a demonstrated and validated floating platform.

1.2 Technology background

The Company was established to investigate and develop new methods of extracting electrical power from tidal currents.

The first prototype of the platform was designed 2008 - 2009 with the aim of fulfilling the following requirements:

- floatability;
- simplicity;
- sturdiness;
- minimal moving parts
- facilitation of maintenance

Significant numbers of alternative designs were assessed during this stage of development, as well as simulations aimed at optimising the platform’s stability under different wave spectra, wind and tidal currents.

Throughout 2010, the knowledge acquired in the previous stages was put into practice to develop a 1:10 scale model of the platform. The scale model was constructed in 2011 and tested during 2012. Both dry dock and sea trials were carried out in Spain and Scotland (EMEC).

With the data obtained from 1:10 scale model, the Company improved the platform design and upgraded the test programme, proving different components integrated into the platform.

All this enabled the further development of a full-scale prototype, whose design began in 2013 and assembly finalised in 2015. This was aimed at moving forward in the optimisation of the platform and, therefore, achieving a more efficient and effective device. This 45-meter floating platform had two 21-meter-high output rotors with a combined capacity of 1.5 MW. The launch of the ‘ATIR’ took place in April 2017, in Vigo, as it can be seen in the figure below.




Figure 1: Evolution of the Magallanes Tidal Energy Technology

During these first prototype tests, we proved and validated the technology, and currently we are focused on the design and development of a fully commercial product based on our existing platform, as well as the validation of our performance, Operations & Maintenance procedures and advancing our manufacturing readiness level.

The final achievement was obtaining high-performance output, with low CAPEX and OPEX costs to demonstrate the most reliable, robust, efficient, proven and competitive platform in the tidal energy market.



Figure 2: Launch of the Prototype ATIR Platform

1.3 Project background

The first full scale prototype ATIR device has been deployed and operated at EMECs Fall of Warness tidal test site, which has enabled us to assess its behavior in real sea conditions throughout the annual seasonality cycle. This testing has allowed us to progress the ATIR towards commercial viability.

This proposed project will see three platforms deployed for up to 25 years at the EMEC Fall of Warness site Berth 4, beginning in 2029. This array will be deployed and operated in parallel to the proposed array in Berth 1

The project aims are as follows:

- Demonstrate the long term operational performance of multiple devices across small arrays of the technology in a real, open sea environment.
- Prove the array electrical architecture for arrays of devices.
- Further verify and validate the commercial version of the technology over long term deployments.
- Provide comfort to potential customers through the operation of multiple devices.
- Demonstrate cost reductions through learnings in multiple deployments, serial manufacture and economies of scale.
- Develop the supply chain and processes for serial manufacture for further, commercial projects.

Data obtained from this period of demonstration will be crucial for the future projects as it provides valuable information regarding long term operation, maintenance, together with electrical performance.

Existing funds have come from two separate funding sources: European Grants and the equity investment from the founder of Magallanes Renovables. These sources will secure the continuous development of Magallanes Renovables technology until its commercialization, as well as the process of securing future projects.

2 Technology

2.1 Device Description

The full scale floating tidal devices to be deployed at EMEC under this proposed project consist of a surface floating platform (upper block), with a nacelle and rotors directly below it (lower block) and a 'mast' (vertical block) connecting the two.




Figure 3: TIR Platform Showing 'Blocks'

This floating tidal energy converter has a total length of 55m, 6m of beam, a minimum draft of 18.5m without blades and 29m with blades. Its maximum weight with ballast is approximately 600tons.



It has two counter-rotating horizontal axis turbines in series, one behind the other, so that it counteracts the efforts of one turbine with those of the other to avoid list and yaw. Each rotor consist of 3 blades with a rotor diameter of up to 24m.




Figure 4: Indicative Overall Dimensions of the Device

Each rotor is equipped with a generator of 850kW of nominal power, and an associated frequency converter; allowing for a peak power of up to 1.7MW; however, the nominal power is limited to 1.5MW.

It's moored to the seabed through four mooring lines, two at each end.

The device is able to orient itself to different directions of current in a passive way and to generate energy efficiently on both the ebb and flood currents.




Figure 5: Main Components of the ATIR Platform

The floating platform (upper block) is the visible part of the device. It has an upper deck, where the entrance hatches are located. It also has 2 inaccessible compartments on both ends of the block, which are part of the variable ballast system. The accessible part of this block is composed of 3 main rooms, the first of them houses pumps and emergency systems, the other 2 have been designed to accommodate transformers, frequency converters, electric panels and other auxiliary electrical or electronic systems.



Figure 6: External View of the Platform (Upper Block)



Figure 7: Internal View of the Upper Block

The mast (vertical block), fixes the nacelle (lower block) to the platform (upper block). It is a hollow space through which the communication and low-voltage cables connect the equipment housed in the nacelle with the parts of the electrical systems within the upper block. Rigid pipes for environmental acceptable lubricant supply and draining, among others, are also installed in the mast. It also allows access to the lower block for inspection and maintenance.



Figure 8: View Looking up into the Mast (Vertical Block) from the Nacelle (Lower Block)

The nacelle (lower block) is significantly smaller than the upper block and is dedicated to the mechanical PTO systems. This block is where the main shafts, gearboxes and generators are located. As the platform is equipped with two counter-rotating rotors, all the components for the PTO system are duplicated (one for each rotor).



Figure 9: Gearbox in the Nacelle (Lower Block)

Each device has electronic power converters onboard the platform that adapts the energy output to the frequency and phase of the network, in addition, they will also have a step-up transformer that will establish the output voltage of each platform at 11kV - the connection voltage).




Figure 10: Diagram of Electrical Power Generation from Tidal Currents

Two options are currently under consideration to connect the platforms to the export cable.

Op1: Ring Connection: the 4 platforms daisy-chained together in a ring, with a single export cable as shown in Figure 11 below. The two ends of the 'ring' will be joined together by a passive subsea hub (/busbar) to ensure that output is not lost for multiple platforms in the event of a cable fault anywhere along the ring. All device interconnection cables will be dynamic cables.

Op2: Star Connection: multiple cable legs connecting the platforms to a single passive subsea hub and export cable, as shown in Figure 12 below. A hybrid version may also be created where the ends of each leg are joined up to make multiple 'rings'. All device interconnection cables will be dynamic cables.

Further optimization modelling will be required to determine the optimum layout for the site.




Figure 11: Ring cable concept




Figure 12: Star cable concept

The export and umbilical cables will be secured / stabilised with the use of up to 30 rock bags (consisting of graded rock in a mesh 'bag') or mattresses (a 'flexible' matrix of linked concrete blocks) up to 8 tonnes each.



Figure 13: Examples of Rock Bags and Concrete Mattresses

2.2 Mooring system

The mooring system consists of 4 mooring lines, 2 at each end fixed to the platform, the mooring lines are redundantly dimensioned so that even if a line breaks, the other line on that side is capable of holding the platform on station.

The following parameters are currently estimated for the site, based on preliminary engineering analysis and modelling undertaken:

- Hull Attachment - A single padeye at the bow and stern, to which a single shackle is connected and from which two mooring lines are attached.
- The chain length from mooring attachment point to anchor: approximately 192.5m (76 and 111mm chain).
- The total length of chain per leg (including excursion limiters): approximately 372.5m.
- Mooring footprint diameter = approximately 500m (250m radius).

See diagram below.




Figure 14: Indicative Scheme for the Mooring System

Anchor systems will be determined through a geotechnical survey. This geotechnical survey may require a separate marine licence or exemption to be obtained from the Licensing Authority prior to undertaking the proposed activity closer to the time. The preferred solution is drilled pile anchors (see below). These are anticipated to be up to 800mm in diameter, 10m long.


The location so the anchors and their exact size has not been determined yet and will be informed by the geotechnical survey.

However, gravity anchors (as detailed lower down) may be used if conditions do not prove suitable for drilled anchors. Magallanes and partner companies have experience with both types of anchor solutions.



Figure 15: Strataloc Anchor (Left). Tricone (Centre) and Core (Right) Anchor Piles that will be considered for use at the site (Developed by Leask Marine)

If gravity anchors are used, these are anticipated to be chain clump weights with a total capacity (wet weight) varying between 90 and 165Te. Anchor sizes will vary due to the statistically derived environmental loading and the larger environmental forces from the North.






Figure 16: Indicative Scheme with Gravity Anchors

Temporary mooring system

A temporary mooring site, at Deerness anchorage, Shapinsay Sound test site or Scapa Bay, will be used for installing and removing the blades before device installation and after removal from the Fall of Warness site respectively. It is most likely that the Deerness anchorage site will be the most favourable due to water depth requirements.

A multicat vessel will be used to tow the device from site to site as and when required. Moorings used at the temporary sites will only be installed for the duration of blade removal works and will be removed shortly after the device has been towed back to Fall or Warness or southwards for maintenance. The temporary mooring locations were chosen due to the relatively benign conditions required for removing the blades which then allows the transportation of the device by towing to Leith docks for maintenance. As the current speeds are still quite considerable at the temporary mooring locations, significant maintenance activities are unable to be performed, hence transportation to a dry dock at Edinburgh.

Details of Deerness anchorage, Shapinsay Sound and Scapa bay sites can be found in section 3.2. The temporary mooring will use a single point mooring system as shown below in the Figure below, due to the less extreme environmental conditions.

A Notice to Mariners will be issued before any works that require the removal of the device from its moorings and transportation to another site.




Figure 17: Single point mooring system schematic prior to device installation (top), and during deployment (bottom)

2.3 Materials used

Materials used in the construction of the devices, together with the mooring systems, are listed in the table below. Please note that around a 20% contingency has been added to the following deposit quantities, and it is expected that the final amounts will be less than those indicated in the table. If a licence is granted, a FEP5 form will be completed after installation to confirm the quantities installed

Table 1: Proposed list of materials to be used

Fall of Warness				
Components	Type of Deposit*	Nature of Deposit (P = Permanent, T = Temporary)	Deposit Quantity (tonnes, m³, etc.)	Contingency Allowance
Platform Structures	Steel	P	2,100 tonnes	20%
Turbine drivetrains	Steel	P	240 tonnes	20%
Rotor blades	Composite	P	60 tonnes	20%
Electrical & control cabinets	Various, largely copper, steel and plastics	P	45 tonnes	20%
Anchors and Mooring lines	Steel	P	7,500 tonnes	20%
Cable	Copper & plastics	P	4,000m	20%
Cable stability	Concrete Bags / mattresses	P	2,400 tonnes	20%
Lubricants	Environmental acceptable lubricant, fulfilling ISO 15380 requirements	P	72 tonnes	20%
Diesel (for emergency power generator)	Diesel	P	6 tonnes	20%
Deerness Anchorage / Shapinsay Sound / Scapa bay				
Components	Type of Deposit*	Nature of Deposit (P = Permanent, T = Temporary)	Deposit Quantity (tonnes, m³, etc.)	Contingency Allowance
Anchors and moorings lines	Steel	T	470 tonnes	20%

*Types of deposits to consider: Steel/Iron; Timber; Plastic/Synthetic; Composite; GRP; Concrete; Silt; Sand; Stone/Rock/Gravel; Concrete Bags/Mattresses; and, Cable.

Please note that all deposits (steel/iron, composite, etc.) referred to as "Temporary" are due to the fact that platforms would be temporarily moored at the Shapinsay Sound scale test site, Deerness anchorage, or and Scapa bay, before they are towed and deployed at Fall of Warness site.

2.4 Third Party Verification (TPV)

With the aim of undertaking the Third Party Verification (TPV) it is proposed to engage the services of Orcades Marine Consultants Ltd, which provides marine project management,

specialist marine risk management, innovative and practical consultancy advice, third party verification and marine warranty survey, independent auditing and assessment to the shipping and port industry, the marine renewable energy sector, and the offshore oil and gas industry. The Company is accredited to ISO 9001 and OHSAS 18001 for the provision of those services to the industry.

Orcades Marine Maritime Consultants has a wide experience in third party verification and marine warranty in the marine renewable sector. Some examples of relevant previous experience includes the following works:

- TPV for a tidal floating system for marine licensing purposes for installation in Orkney
- Independent opinion as to the suitability of a grounding berth for securing a vessel safely alongside
- Marine and safety advisors for the installation of a tidal turbine in Singapore.

Some of their clients in the past have been Tocardo, Sustainable Marine Energy, Aquatera or Andritz Hammerfest.

For all the above, Magallanes Tidal Energy believes that Orcades Marine Consultants is appropriate to conduct the verification of the platforms and their moorings. Such verification will certify the integrity of the structural design of the platforms and their moorings for the conditions expected at the Fall of Warness site, and associated works.

3 Project Description

Key elements of the project.

3.1 Onshore Assets

The array will be connected through a subsea cable to a EMEC's shore-based substation compound on Eday for onward transmission to the National Grid. The subsea cable and substation are already in existence and are owned and operated by EMEC.

3.2 Offshore Location

The array will be deployed at Berth 4 at the EMEC Fall of Warness test site, off the island of Eday, Orkney. This is shown in Figure 18 below. During installation and removal operations, platforms will make temporary use of EMEC's Shapinsay Sound test site, Deerness anchorage or Scapa bay. The more benign conditions found in these temporary locations will facilitate the assembly and disassembly of the rotor blades, as well as the undertaking of other maintenance works, if needed.




Figure 18: Chart showing EMEC’s Fall of Warness test site and the Magallanes deployment area

Magallanes deployment area outlined with solid purple line. Fall of Warness tidal test site Crown Estate lease shown as red line

The space between the devices will require optimising based on detailed array system modelling for the site. An idea spacing would be approximately 275m across the stream as shown below.




Table 2. Location of [Project Name]

Location Description	Latitude and longitude (WGS 84)	UTM (Eastings and Northings)
Deployment site centre point	59°09'25"N , 002°50'25"W	E: 352042 , N:1030318
Test site boundary points	59°09'35"N , 002°50'48"W 59°09'38"N , 002°50'13"W 59°09'21"N , 002°49'57"W 59°09'16"N , 002°50'17"W 59°09'04"N , 002°50'06"W 59°08'58"N , 002°50'26"W	E:351686 , N:1030644 E: 352245 , N:1030721 E: 352492 , N:1030199 E: 352159 , N:1030038 E: 352333 , N:1029657 E: 352013 , N:1029495

3.3 Installation method

The installation method is summarised below.

Fall of Warness mooring works

The mooring systems in the deployment area at the Fall of Warness are described in Section 2.2 above. A pre-installation seabed survey will be undertaken initially to gain a better understanding of the seabed conditions, to determine if drilled anchors (the preferred solution) is feasible and to size the anchors correctly. The survey will consist of ROV or drop camera footage, grab sampling of the seabed and / or core sampling. This information will also be useful for assessing, after the decommissioning of the platforms, whether the site has been left in the same condition as it was before the installation. This survey may require a separate marine licence or exemption to be obtained from the Licensing Authority prior to undertaking the proposed activity closer to the time.

The installation vessel will use a 4-point mooring spread for the duration of all installation activities on site. Installation operations are anticipated to last for a period of no more than 7 days per platform, after which the installation vessel shall recover its moorings and return to shore.

During the installation and subsequent offshore commissioning period, there will also be a daily requirement for a small workboat or RIB for return journeys between the site and Kirkwall Harbour, for transfer of personnel and equipment.

If drilled anchors are used, they will be installed using a submersible drilling rig deployed from a conventional multi-cat type vessel.

- The drill rig will be transported to the deployment site on the deck of a multi-cat.
- Once on site, the vessel will set up on its anchors and the drill rig will be lowered onto the seabed using the vessel crane and levelled using the four independent hydraulic legs.
- Drilling of the anchor to the required depth can then begin.
- If grouted anchors are used, the anchor will be grouted after the drilling is complete (see Section 2.2. for description of different anchor types).




Figure 19: Images Showing drill rig loadout, deployment to seabed and drilling

If gravity anchors (consisting of multiple chain clump weights as shown in Figure 16) are used, these will be deployed from a multicat vessel with sufficient crane capacity to handle the individual clump weights.

Installation operations for the mooring systems and platforms are as described below:

- The multi-cat installation vessel will arrive on site, deploy its mooring spread and set up on the moorings.
- Lengths of ground chain will be deployed and connected (by divers) to each anchor.
- Each chain will then be laid on the seabed as shown in Section 2.2; and then connected to its recovery system (rope and buoy), ready for connection to the platforms.

Fall of Warness electrical works

The array will be connected to the existing Berth 4 export cable, owned by EMEC. A connection management system (passive hub) is expected to be used to connect the individual platform dynamic cable tails to the EMEC export cable in either a star or ring connection as described in Section 2.1

The hub, with cable tails attached will be loaded on a multi-cat vessel. The vessel will sail to the offshore site just off Eday and set up on anchors.

Once at the offshore site, the connector system / hub will be connected to the EMEC export cable and a marker buoy attached to each tail, then lowered onto the seabed for retrieval later.

The hub and cable tails will be secured / stabilised with the use of rock bags or concrete mattresses, as described in Section 2.2.

Blade installation methodology

A platform, without the blades, will be towed by a tug vessel from a safe harbour where final assembly will have taken place, to Shapinsay sound tidal test site, Deerness anchorage or Scapa bay. It is expected the tug vessel will have a length no greater than 31m and draught up to 5m.




Figure 20: Map showing area of EMEC's scale tidal test site, Shapinsay Sound

Table 3: Attachment points at EMEC's Shapinsay Sound test site

Attachment point	Latitude (WGS84)	Longitude (WGS84)
Anchor A	59° 00.200'N	02° 53.073'W
Anchor B	59° 00.165'N	02° 52.918'W




Figure 21: Map showing area of device temporary deployment at Deerness Sound

Table 4: Boundary of lease area for temporary mooring at Deerness anchorage

Attachment point	Latitude (WGS84)	Longitude (WGS84)
Proposed temporary deployment boundary	58° 58.813'N	02° 45.388'W
	58° 58.564'N	02° 45.388'W
	58° 58.564'N	02° 44.829'W
	58° 58.813'N	02° 44.829'W




Figure 22: Map showing area of potential device temporary deployment at Scapa Bay

Table 5: Boundary of lease area for temporary mooring at Scapa Bay

Attachment point	Latitude (WGS84)	Longitude (WGS84)
Proposed temporary deployment boundary	58° 56.17'N	03° 01.61'W
	58° 56.17'N	03° 00.70'W
	58° 55.74'N	03° 00.70'W
	58° 55.74'N	03° 01.61'W

Once the platform is moored at either Shapinsay Sound, Deerness Sound or Scapa Bay, a multicat workboat with a deck crane will load the blades from a port facility around Orkney and transport them to the temporary site. Depending on the deck area, one or more blades may be transported at once.

The vessel will be brought alongside the platform, by means of several slings and the deck crane, one blade will be lifted and lowered into the water until it is located below the upper block of the platform. Once there, with the help of a cable/sling guidance system, the blade will be attached to the underside of the upper block hull. The guidance system also ensures the blade is positioned vertically (with the top of the blade upwards and the root, downwards), just above the nacelle hub. Once the blade is vertical and above the nacelle hub, it will then be lowered using tackles or similar equipment, until the blade root fits in the nacelle hub. The blade will then be bolted to the nacelle hub. Finally, the guidance system will be disengaged from the installed blade, so that it can be used for the assembly of another blade.

Once the first blade is installed, the methodology for assembling the remaining five blades (three blades per rotor) would be the same.

Platform installation

Once the mooring systems for all platforms has been installed and all components and subsystems are fully assembled onto the first platform; that platform will be towed by a tug vessel from Shapinsay Sound test site, Deerness anchorage or Scapa Bay to the Fall of Warness. During the towing, the blades will be locked in order to prevent rotation.

The platform will be attached to the 4 anchor points by means of four chain catenary legs, two at the bow and two at the stern, as described in section 2.2 above.

- The installation multi-cat will set up on its mooring spread.
- The multi-cat, assisted by a workboat will recover the surface buoy of one chain leg and winch in the ground chain, then connect that leg to the padeye on one end of the platform.
- A second chain will then be connected to the same end of the platform in a similar way
- The remaining 2 moorings legs will then be connected to the other end of the platform in a similar manner to that described above.
- Finally, the platform will be connected to its relevant cable tail. The cable tail will be lifted by deck crane from the seabed to the deck of the installation vessel. The cable tail will then be winched onto the platform and connected to the onboard switchgear.

The other platforms will be connected in a similar manner, except that it is likely that subsequent umbilicals will be daisy-chained from one platform to the next.

Magallanes Tidal Energy will work closely with local companies experienced in marine operations, with knowledge of the site and available equipment and vessels to develop detailed procedures for the various activities related to the installation of the platform. It is not known yet the vessels which will be involved for the installation of the platform, due to the characteristics and dimensions of the device, typical workboats or multicat workboats such as MV C-Odyssey, MV C-Salvor, MV C-Chariot, or similar, (with lengths no greater than 28m and draught up to 4m) rather than large installation or heavy lift vessels will be used. In addition, it may be necessary to utilise support vessels (such as MV Ocean Explorer, or similar) for some tasks during the installation of the platforms.



Figure 23: Multi-cat vessels MV C-Odyssey (left) and MV C-Fenna (right)

3.4 Removal method

The removal method will essentially be the reverse of installation using the same multicat type vessels, supported by smaller workboats and a tugboat.

The platform to be removed will be disconnected from its umbilical cable(s) within the platform. The cable end(s) will be capped, buoyed off and lowered onto the seabed. The platform will then be detached from the mooring lines using a multicat workboat and towed by a tug vessel from Fall of Warness test site to one of the temporary sites, where it will be temporarily moored for no more than two weeks.

At the temporary mooring, the blades will be disassembled from the platform by a dive team supported by a multicat workboat with a deck crane. The methodology for detaching the blades from the nacelle hub will be similar to that described in section 3.3 above but in reverse.

For end of life decommissioning, the mooring systems will also be removed, using the crane of one of the vessels participating in the decommissioning operations. If required, a dive team may also help in the recovery of the mooring system. All remaining components which constitute the platform mooring system will be dismantled, on the condition that such removal doesn't entail further disturbance or impact on the environment. The cable end will be lifted by deck crane from the seabed to the deck of the vessel, and the cable reeled back onto the deck of the vessel.

A decommissioning programme will be produced in support of the marine license application, which will outline the decommissioning procedure and associated schedules.

Local companies with experience in marine operations (most probable the company that would have been involved with the installation of the platforms) will participate in removal and decommissioning.

3.5 Anticipated vessel traffic to site

Due to the installation, operation / maintenance and decommissioning of the platform, vessel traffic will be required to and from the Fall of Warness site. Vessels expected to be used are workboats, multicat workboats and support vessels. Listed below are the most significant activities together with the anticipated frequency of vessel movements.

Table 6: Vessel activity associated with the proposed array project

Activity	Anticipated frequency of vessel movements
<i>Installation operations</i>	
Preparation and installation of moorings at Fall of Warness	20 - 40 single day trips
Assembly of blades at temporary anchorage	30 - 40 single day trips
Towing platforms from temporary anchorage to Fall of Warness	4 days preparation 4 days towing operation (2 x vessels)
Installation of platforms (including attachment to moorings and subsea cable connections)	30 - 40 single day trips (possibly over 2 x neap periods)
<i>Operations and maintenance</i>	
Operations and Maintenance on site	Visits at regular intervals. Up to 2 trips per month (1 day trips). During the first month of operation, and in the event of any major repairs required, visits might be more frequent
Towing a platform for maintenance in calmer waters	2 - 3 single day trips per year

Redeployment of a platform at Fall of Warness after maintenance in calmer waters	4 - 6 single day trips per year
Decommissioning	
Decommissioning of the platforms (including unmooring and subsea cable disconnection)	30 - 40 single day trips (possibly over 2 x neap periods)
Towing the platforms from Fall of Warness to temporary Anchorage	4 single day trips
Disassembly of blades	25 - 30 single day trips
Decommissioning of moorings at Fall of Warness	20 - 40 single day trips

It should be noted that all schedules might vary since operations are subject to suitable weather and tidal conditions and, therefore, adverse weather may increase the forecasted duration of activities. Furthermore, it should also be noted that additional trips might be required due to unplanned maintenance. Notices to mariners will be issued prior to undertaking works onsite, specifying the type of works to be carried out and its duration, as well as the vessel(s) involved.

Operations and Maintenance Works

Due to the nature of the platforms, minimal human intervention is required, allowing the platforms to stay on site for long periods of time. This is facilitated by the remotely operated control system and the communication system.

However, during the period the platforms will be deployed, there will be operations and maintenance on site. Visits will take place at regular intervals, up to twice per month, although during the first month of operation, visits may be more frequent.

The platforms have been designed in such a way that there is enough inner space for an accessible machine room, both in the upper block and the lower block. In addition, the lower block is accessible from the upper block through the vertical block. As a result, repairs can be done offshore with no need to take a platform to a shipyard for maintenance. It should be possible to carry out in situ nearly all maintenance activities, dependent on weather and tidal conditions.

In general, the vessels to be used during maintenance works are small support vessels (such as MV Ocean Explorer, or similar), although the use of typical workboats or multicat workboats (assisted by support vessels) will be required for more major maintenance operations.

3.6 Device monitoring systems

The platforms with their subsystems will be monitored continuously in order to ensure proper operation and in order to be able to respond rapidly in case of an emergency. The most relevant device monitoring systems are outlined below, see Table 6.

Table 7: Platform monitoring systems

System	Description
--------	-------------

General monitoring systems	
General position system (GPS)	<p>Records time and date continuously, provides the exact position of the platforms at all times and transmits the information to shore.</p> <p>Each platform will move on the sea surface within an area constrained by its compliant mooring system (based on ebb and flow, depth, length of mooring lines, etc.). In the event that a platform moves outside of its pre-established range, this may mean that there has been a failure in one of the mooring lines. In such case, GPS system will warn immediately about the abnormal position of a platform. This will help to provide a rapid response (with vessels, dive team, etc.) so as to return the platform to a safe and agreed location</p>
Inertial measurement unit (IMU)	Used for monitoring platform stability (pitch, roll and yaw degrees).
Weather station	Records outside temperature, atmospheric pressure, wind speed and wind direction, among others. It helps to anticipate rough weather conditions that may impact on platform behavior.
Insulation monitoring device	Employed in order to monitor the insulation resistance of unearthed main circuits and to detect early deterioration in the insulation.
Current meter	Instrument for providing water velocity data and measurement of local flow conditions in real time.
Specific monitoring systems	
Variable pitch system	Allows the blades' configuration and pitch to change according to the current.
Shaft positioning system	Assures the proper orientation of the rotor blade shaft, so that loads are balanced. It is also intended for facilitating blade assembly and disassembly.
Emergency response systems	
Fire detection system	Set of devices for detecting fire or smoke in the platforms and raising the alarm so as to respond as soon as possible and minimise any damage caused.
Bilge pumping system	If unwanted water is present in a platform, the system is design to drain any watertight compartment, in order to prevent flooding

	and minimise risk of damage due to the presence of internal water.
Uninterruptible power supply system (UPS)	In the event of failure of the grid, this system will provide emergency power to electrical devices so that they can keep running temporarily.
Emergency braking system	If a critical fault takes place and such fault presents a risk to the integrity of a platform, the emergency braking system comes into operation in order to stop the mechanical system and, as a result, stop rotor blade rotation.

Apart from the aforementioned monitoring and response systems, other variables such as temperature, humidity, pressure, voltage, power, etc. will be monitored within the platforms. Furthermore, the main components such as generators, converters and gear boxes, among others, will also be monitored in order to ensure they are working correctly. Two cameras might also be installed on the deck of the platforms, one at the bow and one on the deck, for surveillance purposes.

Owing to the nature of the platforms, which are conceived for minimising required human intervention, a remotely operated system has been developed in order to display and store within the platforms the most relevant parameters. Communication with the platforms is established through the subsea cable(s). Nevertheless, in the event of loss communication, a satellite or radio communication system, which will behave as a redundant system will also be utilised. Both communication systems allow the transmission and operation of the control system variables remotely.

4 Proposed Schedule

Key project dates are as follows:

- Site surveys: Q2 2027 – Q1 2028
- Installation: Q1 – Q2 2029
- Commissioning Q3 -Q4 2029
- Operations: 2029 - 2053
- Decommissioning: 2053