

Method Statement

1. Demolition Phase:

Dismantle the 3 existing damaged sections of existing sea wall which have been subject to failures. Salvage reusable materials, if possible.

2. Foundation Phase:

Place rock Armour adjacent to preexisting concrete haunch. No new haunch will be constructed.

3. Existing Sea Wall Repair Phase:

Select and position stones.

Use appropriate mortar mix to ensure structural integrity.

Pay attention to mortar curing and weather conditions.

Repoint other areas of the wall and infill cavities with concrete where identified.