

ORKNEY ISLANDS COUNCIL ORKNEY LOGISTICS BASE, HATSTON PHASE 1 WORKS SOUTH SIDE RECLAMATION - TYPICAL SECTION

Seabed level varies

Scale 1: 125 1 0 1 2 3 4 5 6 7 8 9 10m SCALE 1:125 at A1

Chart Datum (Kirkwall)	Ordnance Datum (Newlyn)	Quay Heights and Tide Data Hatston Pier, Kirkwall
+6.40m	+5.00m	Quay Edge Level
+3.00m	+1.60m	Mean High Water Spring Tides
+1.40m	0.00m	Ordnance Datum (Newlyn)
+0.60m	-0.80m	Mean Low Water Spring Tides
0.00m	-1.40m	Chart Datum (Kirkwall)
-5.00m	-6.40m	
-7.50m	-8.90m	

-10.00m -11.40m

Phase 1 Works - South Side Reclamation:

Rock armour revetment slope consisting:

Rock Armour Revetment

Seabed level varies

P1	21:02:2023	Preliminary Issue P1 for comment	JJM	
REV	DATE	REVISION	DRN	СНК

Seabed level varies

THIS DRAWING IS COPYRIGHT . DO NOT SCALE FROM THIS DRAWING.



Orkney Logistics Base, Hatston, Orkney

Consenting Process

Phase 1 Works: Typical Cross Section



Civil Engineers Structural Engineers CDM Co-ordinators Geotechnical services Environmental services

Stewart Building, Lerwick, Shetland. ZE1 0LL. Tel: 01595 695512

www.arch-henderson.co.uk - email: lerwick@arch-henderson.co.uk

Aberdeen; Dundee; Glasgow; Lerwick; Inverness; Thurso; Stromness; Southampton; Falkland Islands

DRAWN:	DATE :	CHECKED :	APPROVED :	
JJM	February 2023	SSJ	APS	
SCALE: (A1)		DRAWING STATUS :		
Ass	Shown	Consents		
DRAWING No:	202043/C-	12	REV:	