



Proposed Ground Investigation and Geophysical Works Layout, outside terminal areas [1:20,000]

### Bathymetric Survey Extremities

	Easting	Northing
Gigha	165216.174	647963.619
	165662.908	647783.552
	166117.902	649554.395
	166337.471	649457.099
Tayinloan	168678.011	645975.983
	168678.011	647141.140
	169213.121	645975.983
	169418.591	647141.140

### Geophysical Survey Extremities

	Easting	Northing
Gigha	165320.952	649032.437
	165387.822	648859.537
	165540.340	649161.042
	165622.007	648949.880
Tayinloan	168978.011	646475.983
	168978.011	646641.140
	169273.569	646475.983
	169293.900	646641.140

## Ground Investigation Locations

Reference	Easting	Northing
BH-G01	165451.423	649093.517
BH-G02	165486.113	649073.931
BH-G03	165521.913	649094.120
BH-G04	165519.960	649056.660
BH-G05	165498.993	649025.333
BH-G06	165491.523	648983.271
BH-T01	169116.442	646543.197
BH-T02	169052.268	646555.414
BH-T03	169081.092	646475.983
BH-T04	168978.011	646475.983
BH-T05	168978.011	646601.079
GS-G01	165266.171	648881.026
GS-G02	165298.504	648968.055
GS-G03	165446.815	648997.503
GS-G04	165469.861	649084.551
GS-G05	165607.667	649082.471
GS-G06	165665.265	649159.073
GS-G07	166053.676	648157.682
GS-T01	169165.529	646283.944
GS-T02	169166.558	646392.893
GS-T03	169092.251	646549.710
GS-T04	169148.998	646586.348
GS-T05	169114.881	646591.094
GS-T06	169078.233	646594.245
GS-T07	169264.253	646743.379
GS-T08	169320.814	646820.465
VC-G01	165392.276	648958.965
VC-G02	165374.634	649000.625
VC-G03	165417.641	648995.326
VC-G04	165469.430	648967.000
VC-G05	165432.155	649029.770
VC-G06	165468.980	649022.125
VC-G07	165463.668	649053.304

### NOTES

- Verifying Dimensions.  
The contractor shall verify dimensions against such other drawings or site conditions as pertain to this part of the work.
- Existing Services.  
Any information concerning the location of existing services indicated on this drawing is intended for general guidance only. It shall be the responsibility of the contractor to determine and verify the exact horizontal and vertical alignment of all cables, pipes, etc. (both underground and overhead) before work commences.
- Issue of Drawings.  
Hard copies, dwf and pdf will form a controlled issue of the drawing. All other formats (dwg, dxf etc.) are deemed to be an uncontrolled issue and any work carried out based on these files is at the recipient's own risk. RPS will not accept any responsibility for any errors arising from the use of these files, either by human error by the recipient, listing of un-dimensioned measurements, compatibility issues with the recipient's software, and any errors arising when these files are used to aid the recipient's drawing production, or setting out on site.
- Datum.

### Key

- Proposed Borehole with coring
- Proposed grab sample
- Proposed bathymetric and geophysical survey area
- Proposed bathymetric survey area

<b>P01</b>	Locations revised for Nov tender	CF	26/11/24
rev	amendments	check	date

**rps** Elmwood House  
74 Boucher Road  
Belfast  
BT12 6RZ

T +44 (0) 28 90 667914  
F +44 (0) 28 90 668286  
W [www.rpsgroup.com/ireland](http://www.rpsgroup.com/ireland)  
E [ireland@rpsgroup.com](mailto:ireland@rpsgroup.com)

Client	Argyll and Bute Council	
Project	Gigha and Tayinloan Preliminary Design	
Title	Proposed Ground Investigation Work, Gigha and Tayinloan	
Project Number	Sheet Size	Drawing Scale
IBE02250	A3	1:20,000
Drawing Number	E02250-RPS-XX-XX-DR-C-0003	
Drawn By	Status	Revision
CV	S0	P01
Checked By	Approved By	Date
LMcA	RB	17/04/2024