

Work Schedule

General Items

General items	
Name	Description
G-01	Insurance of the works
G-02	Third Party Insurance
G-03	Mobilisation
G-04	Demobilisation
G-05	Establish Contractor's accommodation, site services and facilities
G-06	Remove Contractor's accommodation, site services and facilities
G-07	Maintain Contractor's accommodation, site services and facilities
G-08	Provision of as-built drawings
G-09	Provision of information for Health and Safety File
G-10	Contractor's supervision
G-11	Temporary works
G-12	Construction Environmental Management Plan
G-13	Pre-Construction Survey
G-14	Comply with conditions of Approvals, Licences and Consents

Main Works

Ground works	
Name	Description
A-01	Survey of the existing beach rock levels to allow the Contractor to provide detailed method statement and drawing showing the proposed construction levels.
A-02	Survey of Railway Jetty prior to commencing works as Contractor is liable for any damage to the Jetty during the construction of the slipway.
A-03	Break out and prepare areas of existing slipway for construction of new including disposal of old concrete/rock, Chainage 0 to Chainage 30m.
A-04	Break out and prepare areas of existing beach rock for construction of new including disposal of bed rock, Chainage 30 to Chainage 90m.
A-05	Drill, grout and install dowels to bed rock as per drawing AMS296_6_16.
Reinforced Concrete (RC) works	
Name	Description
A-06	New RC Sides of slipway (Section CH 0.0 to MHWS). Including excavation, preparation, reinforcement, blinding.
A-07	New RC Sides of slipway (Section MHWS to CH 90). Including excavation, preparation, reinforcement, blinding.
A-08	New RC top deck of slipway (Section CH 0.0 to MHWS). Including excavation, preparation, reinforcement, blinding.
A-09	New RC top deck of slipway (Section MHWS to CH 90). Including excavation, preparation, reinforcement, blinding.
A-10	New hardwood edge protection both sides of slipway (CH 0.0 to CH 90).
A-11	Install Weepholes to new slipway walls
Rock armour	
Name	Description
A-12	Rockfill between new slipway and Railway Jetty, as per drawing AMS296_8_16, (CH25 to MHWS).
A-13	Rockfill between new slipway and Railway Jetty, as per drawing AMS296_8_16, MHWS to CH 90).